

Institute Works Department


Ref. No.: IIT(BHU)/IWD/ET-01/2021-22/350

Dated: 29/07/2021

QUOTATION NOTICE


1. Limited tender quotations are invited from eligible empaneled contractors of EWSS-BHU / UWD-BHU / IWD, IIT (BHU) for **Tender for Electrical Works in the E- HALL of Incubator area IIT(BHU) Varanasi** as per description below. The sealed envelope containing quotation shall be super scribed with the name of the work, tender enquiry ref. no. & date. The quotations will be received up to **06.08.2021 (3:00 P.M.)** in the office of the **Superintending Engineer, Institute Works Department, IIT(BHU), Varanasi.**

S.No	Detail of Items	Qty	Unit	Rate	Amount
1.0	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. (Make: Polycab/ Finolex/ L&T)				
1.1	Group C	40	Points		
2.0	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. (Make: Polycab/ Finolex/ L&T)				
2.1	2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	130	Mtrs		
2.2	2 X 4 sq. mm + 1 X 4 sq. mm earth wire	90	Mtrs		
2.3	2 X 6 sq. mm + 1 X 6 sq. mm earth wire	80	Mtrs		
2.4	4 X 4 sq. mm + 2 X 4 sq. mm earth wire	70	Mtrs		
3.0	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 2 Nos. 3 pin 5/6 A modular socket outlet and 2 Nos. 5/ 6 A modular switch, connections etc. as required. (For light plugs to be used in non residential buildings). (Make: ABB / L&T / Legrand)	30	Nos		
4.0	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 A & 15/16 A modular socket outlet and 15/16 A modular switch, connections etc. as required. (Make: ABB / L&T / Legrand)	20	Nos		
5.0	Supplying and fixing 12 way, Double door, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) (Make: ABB / L&T / Legrand)	1	Nos		
6.0	Supplying and fixing 5 A to 32 A rating, 240 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required . (Make: ABB / L&T / Legrand)				
6.1	Single Pole MCB (Make: ABB / L&T / Legrand)	30	Nos		



Institute Works Department

7.0	DP MCB "C" curve 40/63 A (Make: ABB / L&T / Legrand)	2	Nos		
8.0	DP MCB "C" curve 40/63 A in 2/4 Module sheet Steel Envlosure (Make: ABB / L&T / Legrand)	2	Nos		
9.0	Supplying and fixing 8way (4+24) Double Door, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/ Isolator)	1	Nos		
10.0	63 A "C" curve FPMCB (Make: ABB / L&T / Legrand)	1	Nos		
11.0	32 A "C" curve FP MCB with sheet steel enclosure (Make: ABB / L&T / Legrand)	4	Nos		
12.0	Supplying and fixing 20 A, 240 V, SPN Industrial type socket outlet, with 2 pole and earth, metal enclosed plug top alongwith 20 A "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required. (Make: ABB / L&T / Legrand)	4	Nos		
13.0	Supplying and fixing 20W LED batten (Make: Philips/ Wipro / Polycab)	15	Nos		
14.0	Supplying and fixing 36/40W, 2X2 False ceiling LED Light (Make: Philips/ Wipro / Syska)	22	Nos		
15.0	Supplying and fixing of 230VAC 1Ph. 1400mm dia Ceiling Fan (High Speed) with down rod upto 5ft. (Make: Usha / Crompton / ORIENT)	1	Nos		
16.0	Supplying and fixing of 230VAC 1Ph. Two module steeped type fan electronic regulator	1	Nos		
17.0	Supplying and fixing of 230VAC 1Ph. Wall Fan with sweep feature. (Make: Usha / ORIENT / CG)	10	Nos		
18.0	Supplying and fixing of 230VAC 1Ph. 300 mm exhaust Fan with sweep feature. (Make: Usha / ORIENT / CG)	2	Nos		
19.0	Earthing with G.I. earth pipe 4.5 meter long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required.	1	Nos		
20.0	Providing and fixing 25 mm X 5 mm G.I. strip on surface or in recess for connections etc. as required.	10	Mtrs		
21.0	Supplying and laying of LT power cable of 3.5Cx 50 Sqmm on wall surface including termination at both ends using gland and lugs as required. (Make: Polycab/ Gloster/ KEI)	30	Mtrs		
22.0	150mm dia B class, GI Pipe for Cable laying in road crossing	10	Mtrs		
23.0	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 kV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc. as required				
23.1	Above 95 sq. mm and upto 185 sq. mm	90	Mtrs		
24.0	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 kV grade as required.				
24.1	3½ X 185 sq. mm (57mm)	2	Nos		
24.2	3½ X 35 sq. mm (32mm)	1	Nos		




Institute Works Department

24.3	3½ X 50 sq. mm (32mm)	1	Nos		
24.4	3½ X 95 sq. mm (32mm)	1	Nos		
25.0	SITC of Out door CPRI certified cubical Feeder pilal with EC grade Al busbar capacity 400 Amp 100% neutral suitable >25kA for 3 sec for fault level, compatible for following incoming & outgoing . Incomer detail -SFU-300 Amp,TPN 1 Nos & 3 Nos-HRC fuse Incomer Busbar minimum size-32X3mm. Outgoing Details -SFU-125 Amp,TPN 3 Nos & 9No-HRC fuse,Outgoing Busbar minimum size-25X3mm.	1	Lot		
26.0	Supplying and fixing of 70W Flood/Street LED Light (Make: Philips/ Wipro / Polycab)	2	Nos		
Total Amount (Rs.)					

NOTE:

- Work completion Period - 60 days
 - Amount and quantity variation: Quantity may vary as per actual work execution/site requirement/end user suggested changes during execution but the final bill value shall not exceed more than 5% of order value.
 - Due Date-1 week and Commercial terms & condition as per standard
 - Taxation included as per applicable rule of GST.
 - Warranty period: Defect & Liability period 1 year for all above works after handing over of user certificate.
 - All electrical works shall comply to applicable IS electrical safety norms.
 - Any loss of material/ manpower during the execution of works shall be responsibility of the contractor.
 - For execution of above works all accessories shall be arranged by contractor at their end.
 - Contractor must have valid Electrical Safety Certificate issued by The D.G.- Electrical Safety.
 - Any other losses occurring during the execution of above work shall also be the responsibility of the contractor
 - All works shall be executed by skilled electrician under the supervision of qualified supervisor.
 - Quality of work must comply with CPWD norms.
2. The bidders should submit self certified order copies of similar type of works executed during last three financial years along with self certified copies of satisfactory work completion certificates.
3. Those bidders who have already executed similar type of works in IWD, IIT(BHU) need not submit satisfactory work completion certificates. They should submit only the self certified copies of earlier work orders.
4. The amount of similar work order executed during preceding last three financial years should be at least:



Institute Works Department

(i) 1 order of 80% of estimated cost of this work.

OR

(ii) 2 order of 60% of estimated cost of this work.

OR

(iii) 3 order of 40% of estimated cost of this work.

5. (a) Intending bidder should have average annual financial turnover of at least at least 30% of the estimated cost of this works during preceding last three financial years. **Self certified photocopies of certificate from CA to be submitted with bid.**

(b) Should not have incurred any loss in more than three years during the preceding three financial years ending 31st March, 2021. **Self Certified photocopy of certificate from CA to be submitted alongwith last five years Profit & Loss Account to be submitted with bid.**

(c) Should have a solvency certificate of **40%** of the estimated cost issued by Bank during the last six months. **Certified copy of original solvency certificate to be submitted with bid.**


6. Any bid submitted without the above mentioned documents in support of criteria laid down from Sl. No. 2 to 5 above shall be treated as unresponsive and may not be considered for further evaluation by the tender opening committee.

7. The quotation forms complete in all aspects along with all required documents should be submitted in sealed envelope along with **tender fee of Rs. 590/-** in the form of demand draft drawn in favour of the Registrar, IIT (BHU), payable at Varanasi

8. The estimated cost of this work is **Rs. 4,29,818.00** inclusive of applicable GST. The **earnest money deposit** of **Rs. 13,000.00** shall be submitted in the form of FDR or DD in favour of the Registrar, IIT (BHU), payable at Varanasi. The **EMD** of successful bidder will be retained till the completion of work and shall be returned along with security deposit. The EMD of unsuccessful bidders shall be returned after the final award of work.


9. In case one or more eligible bidders are found lowest that is the L-1 prices are same then all L-1 bidders will be asked to resubmit their bids in sealed envelope with the objective to break the tie cases and determine a single L-1 bidder.

10. The works will be executed on Agreement/work order basis.



Institute Works Department

11. Institute reserves the right to reject any quotation or all quotation without prejudice, assigning any reason or giving any explanation.
12. If quotations are submitted without clearly writing the rates and total amount then quotation shall be rejected.
13. Quotation not stamped & signed by the contractor or his legally authorized agent will be considered invalid.
14. **Security deposit @ 5%** shall be deducted from each bill. The security deposit of 5% deducted from all the bills will be refunded after completion of the warranty period i.e. 12 months from the date of works completion. The date of issue of work completion certificate will be treated as the work completion date.
15. 1% water tax will be deducted from each bill if applicable.
16. Electricity charge will be deducted as per actual consumption, if requirement of electricity for execution of the work.
17. 2% Income Tax and other applicable taxes such as GST etc. shall be deducted as per applicable Govt. rules.
18. **Amount and quantity variation:** Quantity may vary as per actual work execution/site requirement/end user suggested changes during execution but the final bill value shall not exceed more than 5% of order value.
19. All the materials/equipments provided by the vendor will be checked by IWD before installation.
20. **Work completion period:** Within **60 days** from the date of issue of Letter of Award/Work order. Work completion certificate shall be issued by the IWD after obtaining a satisfactory work done report from the user. A period of 10 days will be added to the work completion period for completion of above procedure.
21. **Late work completion penalty:** If work is not completed within the given time, penalty will be deducted as per institute norms.
22. Any damage caused to the building shall have to be made good by contractor at no extra cost & without any delay.



भारतीय
प्रौद्योगिकी
संस्थान
काशी हिन्दू विश्वविद्यालय



INDIAN
INSTITUTE OF
TECHNOLOGY
BANARAS HINDU UNIVERSITY

Institute Works Department

23. The bids submitted after the last date & time will not be considered for opening. The bids received within the last date & time will be opened on **06.08.2021 (4:00 P.M.)** in the Committee room of the Superintending Engineer, IWD, IIT (BHU), Varanasi.

Sd-
Superintending Engineer
Institute Works Department, IIT(BHU)



QUOTATION FORM

Ref. No.: IIT(BHU)/IWD/ET-01/2021-22/350

Dated: 29/07/2021

The Superintending Engineer,
Institute Works Department,
Indian Institute of Technology (BHU)
Varanasi-221005

Subject: Quotation for

.....
.....
.....
.....

Dear Sir,

With reference to the Quotation invited by you for the captioned work. I/We do hereby offer to perform, provide, execute, complete and maintain work in conformity with the drawing, conditions of tender, articles of agreement conditions of contract, specification and quantities of the sum of Rs. _____
(Rupees _____)
_____) at the respective rates mentioned in the quotations.

My/Our quotation will remain open for acceptance for 12 months from the date of its opening.

I have submitting tender fee of Rs. 500/- vide DD No. _____ dated _____ drawn on _____ (Name of Bank).

I have submitted EMD of Rs. _____ Vide FDR/DD No. _____ dated _____ issued by _____ (Name of Bank)

I have enclosed self attached copy of PAN No. and GSTIN alongwith the bid.

My email id for all future correspondence regarding this bid including communication of work order is _____ and mobile no. is _____

(Note: Any information left blank such as email id, mobile number, PAN & GSTIN etc. may lead to rejection of bid as non-responsive)

Yours faithfully,

Date: _____

(Signature of contractor with seal)

